

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


15-065-00511

Company- J.F. DARBY  
Farm- Brandyberry No. 1

SEC. 17 T. 9 R. 22W  
SE SE SW

Total Depth. 4055'  
Comm. 4-30-58 Comp. 5-10-58  
Shot or Treated.  
Contractor. Iron Drlg. Co.  
Issued. 11-22-58

County Graham  
KANSAS



CASING:

Elevation. 2371' KB

Production. DRY

8 5/8" 212' w/150 sx cem.

Figures Indicate Bottom of Formations.

surface soil	215
shale	520
shale, shells	1200
shale, sand	1300
shale, shells	1380
sand	1640
lime shells, red bed	1912
anhydrite	1950
shale, shells	2300
shale, lime	2615
shale	2655
lime, shale	3233
lime	3841
lime, chert	3965
conglomerate	4030
Arbuckle	4050
lime	4055
Total Depth	

TOPS:

Anhydrite	1895
Topeka lime	3375
Heebner shale	3595
Lansing	3630
B/Kansas City	3853
Marmaton	3874
Conglomerate	3956
Arbuckle	4030

Ran Welex log.

DST #1: (Bee Testers) 3644-3672  
Open 1 1/2 hrs; weak steady blow;  
tool rec. 176' wtr; no shows;  
BHP = 1175#/40 mins.; IF = 0;  
FF = 75#; HH = 1900#.