

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

15-005-70245

Company. STANOLIND OIL & GAS CO.
Farm-Titus N. Manning No. 1

SEC. 20 T. 9 R.22W

SW SW NE

2310' S of NL, 2310' W of EL
NE/4

Total Depth. 4082

Comm. 2-29-56

Comp. 3-17-56


Shot or Treated.

Contractor.

Issued. 4-21-56

County Graham

KANSAS



8 5/8 @ CASING: 206' w/ 150 sx cmt.

Elevation. 2396 GL

Production. Dry

Figures indicate Bottom of Formations.

shale & shells	206
shale	800
shale & shells	1260
sand & shale	1320
shale, shells & sand	1460
sand	1675
shale & shells	1790
red bed	1940
anhydrite	1980
shale & shells	2350
shale & lime	2535
lime	2790
lime & shale	3020
lime	3038
shale & lime	3585
lime	3885
lime & shale	3935
lime, chert & shale	3972
cherty conglomerate	4000
lime & shale	4034
lime, shale & chert	4050
lime	4082
Total Depth	

TOPS:

Lansing	3648
Conglomerate	4030
Arbuckle	4046

DST #1: 3555-95, open 40 min. SI 20
min. rec. 1628' muddy SW, no show,
IFP 210#, FFP 865#, BHP 1250#

DST #2: 3676-94, open 1 hr. SI 30 min.
rec. 60' muddy SW, 900' SO&GCSW,
IFP 120#, FFP 455#, BHP 640#

DST #3: 3697-3710, open 1 hr. SI 30 min.
rec. 445' muddy SW, no show, IFP 140#,
FFP 245#, BHP 1190#

DST #4: 3727-50, open 1 hr. SI 30 min.
rec. 545' OCSW, IFP 0#, FFP 270#,
BHP 1200#

DST #5: 3830-40, open 1 hr. SI 30 min.
rec. 95' muddy SW w/ specks of oil,
IFP & FFP 0#, BHP 1160#

DST #6: 4050-82, open 1 hr. SI 20 min.
rec. 2540' muddy SW, IFP 390#, FFP
1180#, BHP 1180#