

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-005-02988


Company- CITIES SERVICE OIL COMPANY
Farm- Holzhauser "A" No. 2

SEC. 23 T. 9 R. 22W
SE SW SE SE
330' N & 855' W of SE Cor.

Total Depth. 3782; PB 3631
Comm. 6-16-54 Comp. 6-25-54
Shot or Treated.

County Graham
KANSAS

Contractor. Lohmann-Johnson Drilg. Co., Inc.
Issued. 8-28-54



CASING:

Elevation. 2344

8 5/8" 240' cem. w/175 sx
5 1/2" 3782' cem. w/175 sx

Production. Phy. Pot. 27 oil,
143 water/24 hrs.

Figures indicate Bottom of Formations.

sand & shale	110
shale	370
shale & sand	1150
redrock	1185
shale & redbed	1826
Anhydrite	1868
shale & shells	2500
shale & lime	2745
shale	2900
shale & lime	3574
lime	3621
lime & shale	3785

3785 RTD = 3782 SIM
Total depth; PB 3631

Tops: Corrected	
Hoebner	3515
Dodge	3535
Lansing	3551
Base Kansas City	3771

3500 gals. acid
Drilled cement to 3763 SIM
Perf. 33 shots 3728-37, no fluid.
Perf. 23 shots 3693-99, 4 gals. muddy
water in 35 mins.
7-1-54: Acidized 750 gals. 3728-37
Acidized 750 gals. 3693-99
Pumped 88 water, no oil, 16 hrs.
Set Lane Wells plug at 3632; 1 gal.
rock on plug; P.B.T.D. 3631 SIM
Perf. 39 shots 3591-3601
Perf. 33 shots 3554-62.
7-4-54: Acidized 1000 gals. 3591-3601
Acidized 1000 gals. 3554-62.