

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 E. Murdock

Wichita, Kansas

15-005-02940


Company - PEEL-HARDMAN
 Farm - GUSTAFSON No. 1

SEC. 25 T. 9 R. 22W
 SW SW SW

Total Depth. 3985
 Comm. 5-3-50 Comp. 5-14-50
 Shot or Treated. 3000 acid
 Contractor. Glenn Pool D_rlg. Co., Inc.
 Issued. 10-21-50

County. Graham

KANSAS



CASING:

8 5/8" 159' com.
 5 1/2" 3760' com.

Elevation. 2359

Production. 132 bbls. oil

Figures Indicate Bottom of Formations.

surface & clay sand	40
sand & shale	120
shale	750
sand	850
shale	975
sand	1190
sand stroak & shale	1335
sand	1585
shale, sholls & sand	
stroak	1852
Anhydrite	1897
shale & sholls	2200
limo & shale	2445
limo & shale stroaks	2525
limo	2725
limo & shale	3065
limo	3495
limo & shale	3535
limo	3985
Total depth	

Scout Tops:

Lansing	3577
Arbuckle	3965

Remarks:

Perf. 36/ 3623-31, 1000 acid;
 Swab. 1 $\frac{1}{2}$ BOFH, 2000 acid,
 5 BOFH