

OPERATOR Sandlin Oil Corp. LEASE Barber

SEC. 26 TWP. 9S RGE. 22

FILL IN WELL INFORMATION AS REQUIRED:

WELL NO. 1

FORMATION DESCRIPTION, CONTENTS, ETC.		TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.					
DST #1: 3616'-42'; 30-30-30-30 1st op, weak dec. blow, died in 4 min. No blow 2nd op. Rec. 10' mud. IFP 35-35#, FFP 35-35# ISIP 104#, FSIP 46#				Anhydrite Topeka Heebner Lansing BKC Marmaton LTD	1844' 3329' 3556' 3597' 3821' 3886' 3929'
DST #2: 3717-87'; 45-45-45-60 Rec. 186' GIP, 25' OCM, 186' MCGO. 1st op weak blow, inc. to 8 1/2". 2nd op weak blow, inc. to 6". IFP 81-104#, FFP 127-138# ISIP 461#, FSIP 461#.					
ACID, FRACTURE, SHOT, CEMENT.					

Amount and kind of material used		Depth interval treated
Frac 10,000 # 20/40 sd, 2500# 10/20 sd, 20,000 gal gel		3888-3904'
Acid w/500 gal muddy acid; re-acid. w/2000 gal SGA		3778', 3798'
Acid w/ 300 gal MCA; re-acid w/2500 gal SGA		3733-3737'
Date of first production 1-18-84	Producing method (Flowing, pumping, gas lift, etc.) pumping	Gravity
Estimated Production -I.P. Oil 25 bbls.	Gas 0 MCF	Water % 8 bbls.
Disposition of gas (vented, used on lease or sold)		Perforations 3733-37'

Report of all strings set— surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface	12 1/4"	8 5/8"	20	218'	common	140 sx	
production	7 7/8"	4 1/2"	11.6	3929'	common	150 sx	

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			1		3888-3904'
TUBING RECORD			1		3859'; 3798'
			2		3778'
Size 2"	Setting depth 3836'	Packer set at	4		3733-3737'
			1		3774-3778'
			SQUEEZE RECORD		3797-3799'

26-9-22W^P

FEB 7 1984

State Geological Survey
WICHITA BRANCH

EMPHASIS OIL OPERATIONS
P. O. Box 506
Russell, Kansas 67665-0506

DRILLERS LOG

OPERATOR: Sandlin Oil Corporation
2300 Security Life Building
Denver, Colorado 80202

CONTRACTOR: Emphasis Oil Operations
P. O. Box 506
Russell, Kansas 67665-0506

LEASE: Barber WELL: #1

LOCATION: NW NW SW
Section 26-9S-22W
Graham County, Kansas

Total Depth: 3930'

Elevation: 2374' K.B.

Commenced: 10-5-83

Date Completed: 10-12-83

Casing: 8-5/8" @ 218' with 140 sks cement
4-1/2" @ 3929' with 150 sks cement

Status: Oil Well

DEPTHS & FORMATIONS

(All measurements from K.B.)

Top Soil & Sand	30'	Shale	3054'
Sand & Shale	1845'	Lime & Shale	3913'
Anhydrite	1881'	Lime (R.T.D.)	3930'

STATE OF KANSAS)
) ss:
COUNTY OF RUSSELL)

Joe K. Branum, of Emphasis Oil Operations, states that the above and foregoing is a true and correct log of the above captioned well, to the best of his knowledge.

Joe K. Branum