

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY

508 EAST MURDOCK - WICHITA, KANSAS

COMPANY CITIES SERVICE OIL CO.

FARM Barber "B"

NO.

1

SEC. 26 T. 9 R. 22W

LOC. NE NE NW

330' S, 330' W of N $\frac{1}{4}$ corner

Graham

COUNTY

TOTAL DEPTH 3789 SLM PB 3628

COMM. 7-16-50

COMP.


7-27-50

SHOT OR TREATED 3000 gals acid.

CONTRACTOR R. W. Rine

ISSUED 12-16-50

KANSAS



CASING

8 5/8" 240' cem w/200 sx.

5 1/2" 3789' cem w/175 sx.

ELEVATION 2342

PRODUCTION Phys. 323 oil,
2% wtr.

FIGURES INDICATE BOTTOM OF FORMATIONS

surface soil, lime,	
shale	240
shale, shells, sand	1825
anhyd.	1860
shale, shells	2070
lime, shale	2350
lime, shale, shells	2695
lime, shale	3345
lime	3790

3790 RTD = 3789 SLM

Total depth PB 3628

Tops:

Topeka	Corr.	3363
Heebner	"	3514
Dodge	"	3536
Lansing	"	3551
Base KC		3773

Drilled cement to 3763 SLM.

Perf. 48 shots 3746-58; bailed

75 gals wtr w/scum oil pr hr for
15 hrs.

8-4-50, acid 1500 gals 3746-58.

8-7-50, pumped 80 oil, 93 wtr, 24 hrs.

8-8-50, pumped 68 oil, 68 wtr, 24 hrs.

Set L-W plug @ 3630; 1 gal rock on
plug; PBTD 3628 SLM

Perf. 48 shots 3587-99.

8-9-50, acid 1500 gals, 3587-99.

8-12-50, pumped 168 oil, 6 wtr, 8 hrs.

DST 3586-97, rec. 90' oil, 60' oil and
gas-cut mud, small showgas.