

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg., Wichita, Kansas


56961
15-005-00024

CITIES SERVICE GAS CO.
Barber No. 1.

SEC. 27 T. 9 R. 22 W
NEc NE
330'S 330'W NE Cor.

Total Depth. 4058'
Comm. 10-18-41 Comp. 11-9-41
Shot or Treated. None
Contractor. Twin Drlg. Co.
Issued. 12-6-41

County. Graham



CASING:
8 5/8" 1582' Cem.

Elevation.

Production. Dry

Figures Indicate Bottom of Formations.

sand & clay	0-80
sand gy sft	110
shale dk & shells	300
shale gy shells	360
lime med	380
shale gy & shells	670
shale green & shells	770
shale & shells	795
sand & iron hd	856
sand & iron shells	925
shale & lime shells	935
sand & iron shells	1070
shale & iron shells	1133
shale blue & lime shells	1220
shale red & shells	1240
sand & iron shells	1275
shale red sticky	1290
shale red & sand	1575
shale & lime shells	1582
shale blue & shells	1640
sdv shale red	1815
lime brkn med	1835
lime lgt hrd	1863
lime gy med	1904
mud red & shells hd	1965
shale gy & shells	2035
shale & lime shells	2233
limo & shale brks	2800
shale & lime shells	2665
lime lgt hrd	2690
lime lgt med	2731
lime gy hrd	2808
lime gy hrd & shale brks	2840
shale red sft	2850
lime lgt hrd	3075
lime & shale brks	3140
shale gy	3157
lime gy hrd	3257
lime & shale brks	3275
shale & shells	3326
lime lgt hrd	3479
lime gy	3535
lime lgt med	3605
lime lgt hrd	3655
lime lgt med	3756
lime gy med	3808
lime lgt hrd	3818
shale & lime	3844
shale & lime shells	3859
lime & shale brks	3885
conglomerate	4058
Total Depth.	

Plot down column

Tops: Lansing	3550
Conglomerate	3880
Arbuckle	4018
Penetration	40