

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-00387

Company- MURFIN DRILLING CO.
Farm- Farrell No. 1

SEC. 32 T. 9 R. 22W
NE NE NW

Total Depth. 4035
Comm. 6-3-52 Comp. 6-25-52
Shot or Treated.
Contractor. Murfin Dlrgr.
Issued. 12-27-52

County Graham
KANSAS



Elevation. 2359 D.F.

Production. Dry

Figures indicate Bottom of Formations.

8" 162'
5" 4035'

shale	60
sand	80
shale	138
sand	145
shale, shells	162
shale	750
shale, sand	1000
shale	1175
shale, sand	1515
sand	1635
red rock	1690
red bed, shale	1875
Anhyd., shale	1920
shale, shells	2310
lime	2320
shale, shells	2500
shale, lime	2710
shale, lime, shells	2825
lime, shale	3035
lime brkn	3105
lime, shale	3180
shale	3305
shale, lime	3340
lime brkn	3410
shale, lime	3585
lime	3970
shale	3998
Congl.	4010
shale, lime	4035
Total Depth	

Tops:
Heebner 3581
Toronto 3604
Mansing-K.C. 3619
Base K.C. 3824
Maraton lime 3856
Maraton chert 3921
Congl. 3998
Arbuckle 4017

Cable-tool information:

Perf. 3809-14 15 shots 5 gal. free oil
in 2 hrs. 1500 gal. acid 1 bbls. oil,
3½ bbl. wtr. per hr. for 3 hrs.

Set plug 3666

Perf. 3655-60 15 shots 7½ bbls. wtr. per
hr. for 2 hrs.

Set plug 3640

Perf. 3621-26 2 bbls. wtr. per hr. for
2 hrs.