

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-005-03020

Company: SASNAK DEVELOPMENT CO.
Farm: Callison No. 4SEC. 35 T. 9 R. 22W
NW SW SW

Total Depth. 3830'


Comm. 8-21-58

Comp. 8-29-58

Shot or Treated.

Contractor. K. & E. Drilling, Inc.

Issued. 11-15-58

County Graham
KANSAS

CASING:

8 5/8" 253' w/150 sx. cem.

5 1/2" 3830' w/100 sx. cem.

Elevation. 2357' KB

Production. 98 BOPD
PHY POT

Figures Indicate Bottom of Formations.

soil & shale	45
sand	65
shale	920
sand	1030
shale and sand	1360
sand	1580
red bed	1840
shale	2245
lime and shale	2625
lime	2740
lime & shale	2880
lime	3080
lime & shale	3516
shale and lime	3595
lime	3830
Total Depth	RTD

TOP: GEOLOGICAL

Heebner	3553
Toronto	3575
Lansing	3589
Base Kansas City	3820

DST #1 3720-3750 Open 1 1/2 hrs. very
weak blow, recovered 120' gas and
heavily gas cut mud 180'
Bottom Hole Pressure 220#

DST #2 3748-3785 Open 1 hr. weak blow, 12
min, recovered 15' mud. Bottom Hole
Pressure 325 #

CABLE TOOLS: Perforated 3662 & 3733 to 3738
3738 Acidized with 3500 gal. Swabbed at
a rate of 3.48 bbls. per hr. of oil
Date of Completion 9-20-58.