



ORIGINAL

33-9s-23w

PHONE 316-792-5968

ENERGY THREE, INC.

P.O. BOX 1505

GREAT BEND, KANSAS 67530

15-065-21263

DAILY DRILLING INFORMATION ...

RICE ESTATE # 4

ELEV. 2464 GR.
2469 K.B.

SE NW SE Sec. 33-9S-23W
GRAHAM COUNTY, KANSAS

9-2-80 MOVED IN LATE P.M.

9-3-80 RIGGED UP, STARTED TO SPUD 7:00 A.M. 9-3-80

9-4-80 DRILLING @ 1430' 7:00 A.M.
SET 263' OF 3 5/8" 28# USED SURFACE PIPE - CEMENTED
WITH 175 SX. COMMON, 2% GEL 3 % C.C. CEMENT CIRCULATED
O.K. PLUG DOWN AT 1:30 P.M. 9-3-80

9-5-80 DRILLING @ 2662' 7:00 A.M.
TOP OF ANHYDRITE 2040' (/ 429)

9-6-80 DRILLING @ 3281' 7:00 A.M.

9-7-80 DRILLING @ 3767' 7:00 A.M.

FORMATION TOPS:	TOPEKA	NOT AVAILABLE
	HEEBNER	3735' (- 1266)
	TORONTO	3758' (- 1289)
	L-KC	3769' (- 1300)

D.S.T. # 1 L-KC "B" ZONE (FROM 3787 TO 3813)
TIMES 30 - 45 - 45 - 60
FAIR TO STEADY BLOW THROUGHOUT TEST
RECOVERED 60' OF MUD W/ SPOTS OF OIL AND
180' MUDDY WATER.
INIT. FLOW 42 - 84
FINAL FLOW 95 - 127
INIT. SHUT IN 686
FINAL SHUT IN 675

9-8-80 3848' AT 7:00 A.M. RUNNING D.S.T. # 2 3825 TO 3848.
(L-KC "F" ZONE)

(CONT.)

RECEIVED
MAY 13 1981
15-065-21263



ORIGINAL

PHONE 316-792-5968

ENERGY THREE, INC.

P.O. BOX 1505

GREAT BEND, KANSAS 67530

DAILY DRILLING INFORMATION

RICE ESTATE # 4

PAGE -2-

9-8-80 (CONT.)

D.S.T. # 2

TIMES 30 - 45 - 45 - 60

WEAK BLOW THROUGHOUT. RECOVERED 120' OF THIN MUD - NO SHOW OF OIL.

INIT. FLOW 42 - 42

FINAL FLOW 52 - 74

INIT. SHUTIN 265

FINAL SHUTIN 255

9-9-80

3858 AT 7:00 A.M. RUNNING D.S.T. # 3

3844 TO 3858 (L-KC "G" ZONE)

TIMES 30 - 45 - 45 - 60

FAIR BLOW THROUGHOUT. RECOVERED 60' OF GAS, 30' OF OIL & GAS CUT MUD, 90' OF SLITELY OIL & GAS CUT WATERY MUD.

INIT. FLOW 31 - 42

FINAL FLOW 42 - 63

INIT. SHUTIN 275

FINAL SHUTIN 264

D.S.T. # 4 3910' TO 3932' (L-KC "I" ZONE)

TIMES 30 - 45 - 60 - 60

STRONG BLOW THROUGHOUT. RECOVERED 20' OF OIL CUT MUD; 60' OF VERY MUDDY GASSY OIL; 60' OF SLITELY MUDDY GASSY OIL.

INIT. FLOW 52 - 52

FINAL FLOW 63 - 84

INIT. SHUTIN 307

FINAL SHUTIN 307

9-10-80

3952 AT 7:00 A.M. RUNNING D.S.T. # 5

3940 TO 3952 (L-KC "J" ZONE)

TIMES 30 - 30 - 30 - 30

VERY WEAK BLOW FOR 20 MINUTES, RECOVERED 30' OF MUD - NO SHOW OF OIL.

INIT. FLOW 31 - 42

FINAL FLOW 42 - 42

INIT. SHUTIN 84

FINAL SHUTIN 52

(CONT.)

1000-10-10-80
GREAT BEND, KANSAS
67530



ORIGINAL

ENERGY THREE, INC.

P.O. BOX 1505

GREAT BEND, KANSAS 67530

DAILY DRILLING INFORMATION

RICE ESTATE # 4

PAGE -3-

9-10-80 (CONT.) D.S.T. # 6 3945 TO 3970 (L-KC "K" ZONE)
TIMES 30 - 45 - 60 - 60
STRONG BLOW THROUGHOUT TEST. RECOVERED 30'
OF VERY SLITELY OIL CUT MUD; 120' OF SLITELY
OIL CUT THIN MUD; 780' OF WATER.
INIT. FLOW 42 - 190
FINAL FLOW 201 - 413
INIT. SHUTIN 1145
FINAL SHUTIN 1114

9-11-80 3970' AT 7:00 A.M. (HAD JUST FINISHED DST # 6)

9-12-80 T. D. 4008'. SET 4 1/2" CASING @ 4000' CEMENTED
WITH 125 SX. FINISHED @ 5:00 A.M. 9-12-80.
TORE DOWN, MOVED OFF.

RECORDED
INDEXED
KANSAS
OCT 1 1980