


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- IMPERIAL OIL OF KANSAS, INC.
Farm- McPherson No. 2

15-005-02798
SEC. 4 T. 9 R. 23W
C NW SE

Total Depth. 3824
Comm. 4-30-55 Comp. 5-8-55
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 7-30-55

County Graham
KANSAS



8 5/8 @ CASING: 229' w/ 150 sx cmt.
5 1/2 3825' cmtd.

Elevation. 2258 RB

Production. 636 BOPD, NW

Figures indicate Bottom of Formations

sand rock & clay	229
surface clay & shale	670
sand & shale	1395
Dakota sand	1645
red bed & shale	1893
anhydrite	1930
shale & shells	2835
shale & lime	3555
lime	3824
Total Depth	

TOPS:	
Anhydrite	1893
Heebner	3541
Lansing	3582

DST #1: 3602-20, open 1 hr. rec. 2000'
SW, IFP 60#, FFP 890#, BHP 1280#/20
min.

DST #2: 3710-26, open 1 hr., rec. 3000'
gas, 560' free oil, IFP 30#, FFP 210#
BHP 1180#/20 min.

DST #3: 3740-58, open 1 hr., rec. 3'
mud, BHP 0#/20 min.

DST #4: 3781-98, open 1 hr., rec. 5'
mud, BHP 0#/20 min.