

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-02799

Company- IMPERIAL OIL of KANSAS, INC.
Farm- McPherson No. 3

SEC. 4 T. 9 R. 23W
C S $\frac{1}{2}$ SW NW

Total Depth. 3771'
Comm. 4-7-56 Comp. 4-16-56
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 7-21-56

County Graham
KANSAS



CASING:

8 5/8" 203' w/200 sx cem.
5 1/2" 3764' cem.

Elevation. 2255' RB

Production. 36 BOPD, NW.

Figures Indicate Bottom of Formations.

clay-sand	115
shale	935
sand	1140
shale	1350
red bed	1510
sand-shale	1640
shale	1685
shale-red bed	1895
Anhydrite	1925
shale	1955
shale-shells	2285
lime-shale	2385
shale	2515
lime-shale	2875
lime	3230
lime-shale	3490
lime	3764 RTD
lime	3771
Total Depth	

TOPS:

Anhydrite	1895
Heebner	3539
Toronto	3563
Lansing	3580

DST #1 - 3704-24 Open 1 hr.,
rec. 960' wtr. Trace
of oil. FP 30# - 375#
BHP 700#.

DST #2 - 3736-63 Open 1 hr.,
rec. 1860' gas, 275'
oil. bhp 840#.