

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-00984

Company- IMPERIAL OIL OF KANSAS, INCORPORATED
Farm- Stagers No. 1

SEC. 5 T. 9 R. 23W
SE SE NW

County Graham
KANSAS

Total Depth. 3860'


Comm. 2-25-57

Comp. 3-15-57

Shot or Treated.

Contractor. Imperial Oil of Kansas, Incorporated

Issued. 5-18-57



Elevation. 2287' RB

Production. Dry

CASING:

8 5/8" @200' w/175 sx cem.

5 1/2" @3860'

Figures indicate Bottom of Formations.

surface clay & sand	200
sand & shale	1465
Dakota Sand	1675
shale & shells	1765
shale & red bed	1935
Anhydrite	1978
shale & shells	2560
shale & lime	3513
lime	3860 RTD

Total Depth

TOPS

Anhydrite	1935
Heebner	3585
Toronto	3610
Lansing	3627

DRILL STEM TESTS

DST #1 3665-84' op. 1 hr.

Rec. 5' mud. BHP 0#.

DST #2 3693-3711' op. 1 hr.

Rec. 15' mud BHP 1030#.

DST #3 3766-83' op. 2 hrs.

Rec. 450' gas, 30' oil cut
mud, 60' heavy oil cut mud.
BHP 830#.

DST #4 3794-3807' op. 1 hr.

Rec. 15' mud. BHP 30#.

DST #5 3802-28' op. 1 hr.

Rec. 12' mud BHP 30#.