

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

15-005-02810

Company- IMPERIAL OIL OF KANSAS, INC.

Farm- Beiker "B"

No. 3

SEC.

9

T. 9

R. 23W

NW SW NE

Total Depth. 3910'

Comm. 9-5-57

Comp. 9-24-57


Shot or Treated.

Contractor. Imperial Oil of Kansas, Inc.

Issued. 12-14-57

County Graham

KANSAS



Elevation. 2374' RB

Production. 261 BOPD, NW

CASING:

8 5/8" 216' cem w/175 sx.

5 1/2" 3910'

Figures indicate Bottom of Formations

hard rock & sand	160
shale & sand	1500
Dakota sand	1725
red bed & shale	1970
shale & shells	1995
Anhydrite	2037
shale & shells	2235
shale	2455
shale & lime	3662
lime	3910 RTD
Total Depth	

TOPS:

Anhydrite	2012
Heebner	3656
Toronto	3678
Lansing	3691
Base Kansas City	3905

DRILL STEM TESTS:

#1 3716-32', open 2 hrs. gas to surface in 1 hr and 14 min. Recovered 2,410' of clean oil (34 gravity) BHP 1330#/20 min.

#2 3733-36', open 2 hrs., strong blow for 2 hrs. Recovered 2,000' of gas and 1,090' of very gassy oil (32 gravity) BHP 1330#/20 min.

#3 3756-67', open 2 hrs., recovered 60' gas, 30' oil cut mud. BHP 65#/20 min.