

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-02179

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Beiker "B" No. 5

SEC. 9 T. 9 R. 23W
 SW SE NE

Total Depth. 3891'
 Comm. 10-25-57 Comp. 11-5-57
 Shot or Treated.
 Contractor. Imperial Oil of Kansas, Inc.
 Issued. 1-11-58

County Graham KANSAS



CASING:

8 5/8" @ 217' cem. w/1957 sx

Elevation. 2344.1 KB

Production. Dry

Figures indicate Bottom of Formations

surface clay & sand	217
sand & shale	1515
Dakota Sand	1725
shale & red bed	1990
anhydrite	2033
shale & shells	2485
shale & lime	3405
lime	3891 RTD
Total Depth	

TOPS: (Electric Log)

Anhydrite	1990
Heebner	3637
Toronto	3660
Lansing	3673

D.S.T. #1. 3697-3710 Open 1 hr. Rec.
 10' mud. BHP 30#.
 D.S.T. #2. 3710-17 Open 1 hr. Rec.
 15' mud. BHP 50#.
 D.S.T. #3. 3735-47 Open 1 hr. Rec.
 8' mud with specks of oil. BHP 50#.
 D.S.T. #4. 3747-55 Open 2 hrs. Rec.
 100' muddy salt wtr. BHP 1150#.
 D.S.T. #5. 3791-3814 Open 1 hr. Rec.
 12' mud. BHP 30#.
 D.S.T. #6. 3812-32 Open 1 hr, rec.
 15' mud. BHP 30#.
 D.S.T. #7. 3846-70 Open 1 hr. Rec.
 10' mud. BHP 0#.