

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02098

Company- CHAMPLIN OIL & REFINING CO.
Farm- Earl Radcliffe No. 3

SEC. 9 T. 9 R.23W
NW SE SE

Total Depth. 3900'
Comm. 8-6-63 Comp. 8-15-63
Shot or Treated.
Contractor. Red Tiger Drilg.
Issued. 12-7-63

County Graham
KANSAS



Elevation. 2338' DF

CASING:

8 5/8" 264.84' Cem w/ 200 sx

Production. DRY

Figures Indicate Bottom of Formations.

surface sand & shale	275
shale & shells	1525
sand	1730
shale & shells	1845
shale, shells & sand	1915
anhydrite	2015
red bed & shale	2345
lime & shale	3555
lime	3900
Total Depth	

TOPS: LOG

Heebner	3637
Toronto	3660
Lansing- Kansas City	3675
Zone "B"	3707
Zone "D"	3718
Zone "E"	3742
Zone "F"	3746
Zone "G"	3752
Zone "G"	3794
Zone "H"	3806
Zone "I"	3828
Zone "J"	3842
Zone "K"	3862
Zone "L"	3877
Base Kansas City	3891

DST #1 3707-20 Open 2 hrs.
Opened with a weak blow for 5 min. and died. Rec. 10' oil specked mud.
ISIP 353# 30 min; FSIP 47# 60 min; IFP 20#; FFP 28#; IHP 1982#; FHP 1974#; BHT 114°F

DST# 2 3720-48 Open 2 hrs. Opened with a fair blow which lasted throughout test Rec. 110' slightly oil and gas cut water; mud. 110' muddy water 180' saltwater
ISIP 1189# 30 min; FSIP 832# 60 min;
IFP 31#; FFP 196#; IHP 2038#; FHP 2022#;
BHT 115°F

DST# 3 3795-3830 Op 2 hrs. Opened with a weak blow for 4 min and died., flushed tool after 5 min. No blow. Rec. 10' mud No show. ISIP 974# 30 min; FSIP 675# 60 min; IFP 28#; FFP 39#; IHP 2062#; FHP 2046#
BHT 114°F