

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

15-005-02182


Company- IMPERIAL OIL of KANSAS, INC.  
Farm- Robinson "B" No. 1

SEC. 16 T. 9 R. 23W  
NW NW SW

Total Depth. 3955'  
Comm. 2-2-58 Comp. 2-12-58

County Graham  
KANSAS

Shot or Treated.  
Contractor. Imperial Oil of Kansas, Inc.  
Issued. 3-22-58



CASING:  
8 5/8" 219' cem w/150 sx

Elevation. 2415' RB

Production. Dry

Figures indicate Bottom of Formations.

surface clay & sand	170
shale	219
shale, shells & sand	890
shale & sand	1400
shale	1595
sand	1780
shale & red bed	1840
shale & shells	2030
Anhydrite	2065
shale & shells	2390
shale & lime	3500
lime	3955-RTD
Total Depth	

TOPS: SAMPLE

Anhydrite	2030
Heebner	3703
Toronto	3728
Lansing	3741

NO ELECTRIC LOG RUN.

D.S.T. #1, 3878-96, Open 1½ hours, recovered 25' mud, BHP 0#.  
D.S.T. #2, 3913-55, Open 2 hours, recovered 50' oil cut mud,  
BHP 130#.