

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-005-02821

Company- IMPERIAL OIL OF KANSAS, INCORPORATED SEC. 17 T. 9 R. 23W
 Farm- Robinson "A " No. 2 SE NW SE

Total Depth. 3925'

Comm. 2-6-57


Comp. 4-26-57

Shot or Treated.

Contractor. Imperial Oil of Kansas, Inc.

Issued. 5-18-57

County Graham
 KANSAS



Elevation. 2380' RB

Production. 287 BOPD 30% Wtr.

CASING:

8 5/8" @185' w/150 sx cem.

5 1/2" @3925'

Figures indicate Bottom of Formations.

surface sand & clay	185
sand & shale	1535
Dakota Sand	1760
shale & red bed	1998
Anhydrite	2041
shale & shells	2300
shale & lime	3410
lime	3925 RTD
Total Depth	

TOPS

Anhydrite	1998
Heebner	3656
Toronto	3683
Lansing	3697

DRILL STEM TESTS

DST #1 3719-37' op. 1 hr.

Rec. 325' salt water.

BHP 1150#.

DST #2 3820-40' op. 1 hr.

Rec. 10' mud BHP 0#.

DST #3 3840-60' op. 1/2 hr.

Rec. 2000' gas, 320' oil.

BHP 975#.

DST #4 3883-3908' op. 1 hr.

Rec. 2800' gas, 1200' oil.

BHP 1150#.