

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-005-02823

Company- IMPERIAL OIL OF KANSAS, INCORPORATED
 Farm- Robinson "A" No. 5

SEC. 17 T. 9 R. 23W
 C SW NE

Total Depth. 3925'

Comm. 3-14-57


Comp. 4-16-57

Shot or Treated.

Contractor. Imperial Oil of Kansas, Incorporated

Issued. 5-25-57

County Graham
 KANSAS



CASING:

8 5/8" @188' w/150 sx cem.

5 1/2" @3925'

Elevation. 2394' RB

Production. 1906 BOPD, No Wtr.

Figures indicate Bottom of Formations

surface clay & sand	188
sand & shale	1555
Dakota Sand	1785
shale & Red Bed	2015
Anhydrite	2054
shale & shells	2530
shale & lime	3635
lime	3925 RTD
lime	3927

Total Depth

TOPS

Anhydrite	2015
Heebner	3667
Toronto	3690
Lansing	3709

DRILL STEM TESTS

DST #1 3729-49' Op. 1 hr.

Rec. 1000' gas, 60' heavily
 oil cut mud, 75' muddy oil,
 240' oil. FP 25#-160#.

BHP 1330#.

DST #2 3854-70' Op. 1/2 hr.

Gas to surface in 30 min.

Rec. 60' heavily oil cut
 mud, 2544' free oil.

FP 180#-730#. BHP 930#.