

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02828

Company- IMPERIAL OIL of KANSAS, INC.
Farm- Robinson "A" No. 11

SEC. 17 T. 9 R. 23W
SE SE NE

Total Depth. 3965'
Comm. 11-19-57 Comp. 12-7-57
Shot or Treated.
Contractor. Imperial Oil of Kansas, Inc.
Issued. 3-1-58

County Graham
KANSAS



CASING:
8 5/8" 211' cem w/175 sx
5 1/2" 3965'

Elevation. 2434' RB

Production. 240 BOPD, 0% Wtr.

Figures indicate Bottom of Formations.

surface sand & clay	210
sand	370
sand & shale	1140
shells & shale	1555
Dakota Sand	1810
shells & shale	2009
Anhydrite	2055
shale & shells	2165
shale	2460
shale & lime	3405
lime	3965-RTD
Total Depth	

<u>TOPS:</u>	<u>SAMPLE</u>	<u>ELECTRIC</u>
Anhydrite	2009	
Heebner	3716	3714
Toronto	3739	3739
Lansing	3752	3752

Samples were examined from 3500 to RTD.

D.S.T. #1, 3775-89 Open 1 hour. Rec.
275' gas, 145' heavy oil
cut mud, 60' muddy oil, 60'
oil cut salt water, 300'
salt water. BHP 1090#.

D.S.T. #2, 3896-3914, Open 1 hour. Rec.
1105' gas, 340' oil. BHP 370#.

D.S.T. #3, 3929-65 Open 1 hour. Rec. 20'
mud. BHP 30#.