

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-005-02830

Company- IMPERIAL OIL OF KANSAS
 Farm- Robinson "A" No. 14

SEC. 17

T. 9


R. 23W

NW SE NW

Total Depth. 3860'
 Comm. 7-12-58 Comp. 7-22-58
 Shot or Treated.
 Contractor. Imperial Oil of Kansas
 Issued. 10-4-58

County Graham

KANSAS



CASING:

8 5/8" 220' w/150 sx. cem.
 5 1/2" 3859' w/100 sx. cem.

Elevation. 2322' RB

Production. State Potential:
 107 BOPD - NW
 Grav. 38°

Figures indicate Bottom of Formations.

sand & shale	220
shale, sand and shells	1050
shale & shells	1935
anhydrite	1969
shale & shells	2410
shale & lime	3645
lime	3860 RTD
Total Depth	

TOPS	ELECTRIC LOG	
Anhydrite	1935	
Hoeblers	3601	3601
Toronto	3625	3624
Laussing	3641	3640
Base Kansas City	3859	
Rotary Total Depth	3860	3859

DST #1 3663-73 Open 2 hrs. Recovered 120' gas, 45' oil cut mud, 90' muddy water, ICIP 1315#.

DST #2 3677-84 Open 1 hr. Recovered 180' gas, 40' free oil, 200' heavy oil cut water, 2300' slightly oil cut water, ICIP 1355#.

DST #3 Open 1 hr. Recovered 575' salt water, BHP 1230#.

DST #4 Open 1 hr. Recovered 10' mud, BHP 0#

DST #5 3817-60 Open 2 hrs. Recovered 320' oil, BHP 300 #.