

65773

SIDE TWO

Operator NameChief Drilling Co., Inc.... Lease Name...Albers.....Well #..1....

Sec...20.... Twp...9S.... Rge..23.W... County.....Graham.....

WELL LOG

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all drill stem tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface during test. Attach extra sheet if more space is needed. Attach copy of log.

Drill Stem Tests Taken [X] Yes [] No
Samples Sent to Geological Survey [X] Yes [] No
Cores Taken [] Yes [X] No

Formation Description

[X] Log [X] Sample

3-12-85 DST #1 3741 - 3783 (Lans. 35 & 50) 30-30-30-30 blow died in 27 min., no afterblow, Rec. 15' M IBHP: 618 FBHP: 609 Hydr. 1926-1901 IFP: 69-51 FFP: 64-51
3-13-85 Drilling @ 3800' DST #2 3785-3815 (Lans. 70 & 90) 30-30-30-30 wk. blow died in 14 min., Rec. 300' GIP: 10'M; IBHP: 137#, FBHP: 64#, Hydro. 1926-1917 IFP: 51-42 FFP: 45-42
3-14-85 Drilling @ 3873' RTD 3945'
3-15-85 Plugged w/180 sx. 50-50 posmix, 6% gel, 3% c.c., 1st plug @ 1890' w/20 sx., 2nd plug @ 1190' w/100 sx., 1 bag of celloflake, 300 sx. w/30 sx. solid bridge @ 40' w/10 sx., 10 sx.
3-16-85 rat hole, Started 1:30 a.m. Completed 3:50 a.m. David Wand State Plugger District #6

Table with columns: Name, Top, Bottom. Includes FORMATION TOPS and E-LOG TOPS with values for Anhydrite, Heebner, Toronto, Lansing, Muncie Cr., Stark, Hush Puckney, and LTD.

Well log table with columns: Name, Top, Bottom. Includes surface sand/clay, sand/clay, anhydrite, shale, shale/lime, lime, and RTD.

CONFIDENTIAL

CASING RECORD [X] New [] Used

Report all strings set-conductor, surface, intermediate, production, etc.

Table with columns: Purpose of String, Size Hole Drilled, Size Casing Set (in O.D.), Weight Lbs/Ft., Setting Depth, Type of Cement, #Sacks Used, Type and Percent Additives. Includes handwritten entry for surface posmix, 2% gel, 3% c.c.

PERFORATION RECORD

Acid, Fracture, Shot, Cement Squeeze Record

Table with columns: Shots Per Foot, Specify Footage of Each Interval Perforated, (Amount and Kind of Material Used), Depth. This section is crossed out with a large X.

TUBING RECORD table with columns: Size, Set At, Packer at, Liner Run, Yes/No.

Date of First Production, Producing Method table with options: Flowing, Pumping, Gas Lift, Other (explain).

State

CHIEF DRILLING CO., Inc.

Drilling Contractors - Oil Producers

SUITE 905 CENTURY PLAZA
WICHITA, KANSAS 67202

V. RICHARD HOOVER
PRESIDENT

DAILY DRILLING REPORT
RIG #1
API: 15-065-22,154

(316) 262-3791

CONFIDENTIAL
APR - 5 1985
State Geological Survey
WICHITA BRANCH

ALBERS #1 (#2284)
NE SW NE Sec. 20-9S-23W
GRAHAM COUNTY, KANSAS

ELEVATION: 2386 GR.
2388 D.F.
2391 K.B.

- 3-07-85 Started moving in on location
- 3-08-85 Finished moving in on location
spudded in @ 5:00 p.m. ran 6 jts.
new 20#, 8 5/8" 254', set @ 260',
cemented w/180 sx. 60-40 posmix,
2% gel, 3% c.c., cemented from
9:30 p.m. - 10:00 p.m.
- 3-09-85 Drilling @ 532'
- 3-10-85 Drilling @ 2427'
- 3-11-85 Drilling @ 3074'
- 3-12-85 Drilling @ 3658' DST #1 3741 - 3783
(Lans. 35 & 50) 30-30-30-30 blow
died in 27 min., no afterblow, Rec. 15' M
IBHP: 618 FBHP: 609 Hydr. 1926-1901
IFP: 69-51 FFP: 64-51
- 3-13-85 Drilling @ 3800' DST #2 3785-3815
(Lans. 70 & 90) 30-30-30-30 wk. blow
died in 14 min., Rec. 300' GIP: 10'M;
IBHP: 137#, FBHP: 64#, Hydro. 1926-1917
IFP: 51-42 FFP: 45-42
- 3-14-85 Drilling @ 3873' RTD 3945'
- 3-15-85 Plugged w/180 sx. 50-50 posmix, 6%
gel, 3% c.c., 1st plug @ 1890' w/20
sx., 2nd plug @ 1190' w/100 sx.,
1 bag of celloflake, 300 sx. w/30 sx.
solid bridge @ 40' w/10 sx., 10 sx.
- 3-16-85 rat hole, Started 1:30 a.m. Completed
3:50 a.m. David Wand State Plugger
District #6

FORMATION TOPS:

Anhydrite	1990	+	401
Base Anhydr.	2024	+	367
Heebner	3684	-	1293
Toronto	3708	-	1317
Lansing	3724	-	1333
Muncie Cr.	3840	-	1449
Stark	3902	-	1511
Hush Puckney	3922	-	1531
RTD	3945	-	155'

E-LOG TOPS:

Anhydrite	1985	+	406
Base Anhydr.	2020	+	371
Heebner	3690	-	1299
Toronto	3717	-	1326
Lansing	3731	-	1340
Muncie Creek	3848	-	1457
Stark	3908	-	1517
HushPuckney	3928	-	1537
LTD	3948	-	1557

JUL 1 1986

State Geological Survey
WICHITA BRANCH

RECEIVED
STATE CORPORATION COMMISSION

MAR 21 1985

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

APR 0 1985

CONSERVATION DIVISION
Wichita, Kansas