

KANSAS GEOLOGICAL SOCIETY
KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
KANSAS GEOLOGICAL SOCIETY BUILDING
508 EAST MURDOCK - WICHITA, KANSAS

15-005-20156

COMPANY ABERCROMBIE DRILLING

SEC. 20 T. 9 R. 23W
LOC. SW NE SW

FARM Ernst

NO. 1

TOTAL DEPTH 3987'

COMM. 6-28-68

COMP. 8-15-68


SHOT OR TREATED

CONTRACTOR Abercrombie Drig.

ISSUED 10-19-68

COUNTY Graham

KANSAS



CASING

20 10
15 8 5/8"
12 EX 7" 253' cem w/ 75 sx
13 5
4 1/2" 3984' cem w/ 125 sx

ELEVATION 2426' KB

PRODUCTION P 102 BOPD, NW
Lans 3832-36 & 3802 -05

0	40	Sandstone
40	215	Sand & Clay
215	913	Shale
913	1270	Sand Streaks & Shale
1270	1600	Shale & Sand Streaks
1600	1778	Sand
1778	2031	Red Bed Shale
2031	2071	Anhydrite
2071	2335	Shale
2335	2600	Shale & Lime Streaks
2600	2870	Shale
2870	3190	Lime & Shale
3190	3275	Lime
3275	3709	Lime & Shale
3709	3985	Lime
	3985	Rotary Total Depth
	3987	LTD

Drilled 260' of 9" surface hole and set 7" casing @253' w/75 sx. Sunset cement.
Cement circulated. Plug was down June 28, 1968.
Set 4 1/2", 10 1/2" Casing @3984' w/125 sx. salt-saturated 50/50 posmix cement.
Plug was down July 6, 1968.

ELEVATION: 2426 K. B.
2424 D. F.
2418 G. L.

TOPS: LOG
Anhydrite (s) 2031
Heebner 3725
Toronto 3749
Lansing 3764
Base Kansas City 3985
RTD 3985
LTD 3987