

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-00741

Company- E. K. CAREY DRILLING CO., INC.
Farm- Denning No. 1

SEC. 23 T. 9 R. 23W
SW SW SE

Total Depth. 4228'
Comm. 2-21-55 Comp. 3-6-55
Shot or Treated.
Contractor. E. K. Carey Drlg.
Issued. 4-9-55

County Graham
KANSAS



Elevation. 2400' DF

Production. Dry

Figures indicate Bottom of Formations. K. B.

CASING:
8 5/8" 192' cem w/100 sx

cellar	7
shale and shells	70
sand	105
shale and lime	192
shale and shells	725
shale, shells & sand	1350
shale and shells	1525
sand	1700
shale and shells	2000
anhydrite	2035
shale and shells	2170
shale and lime	2320
lime and shale	2765
lime	3250
sand and shale	3310
lime and shale	3450
lime	3690
brown lime	3709
K. C. lime	3740
lime	3935
shale	3982
shale and lime	4030
lime and shale	4215
lime	4228
Total Depth	

Tops:	
Hebner	3676
Toronto	3696
Lansing	3709
Base Kansas City	3935
Marmaton Chert	4027
Cherty Conglomerate	4132
Simpson	4209
Arbuckle	4215

DRILL STEM TESTS:

#1 3702-3765 or 63' anchor. tool open 1 hr.
& 10 min. Closed 20 min. for BHP. Rec. 90'
salt water. BHP 1120# FFP 70# IFP zero.