

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-30354

Company. BURCH DRILLING CO., INC.
 Farm. Goddard No. 1

SEC. 23 T. 9 R. 23W
 SE SE NW

Total Depth. 3940'
 Comm. 7-6-59 Comp. 7-14-59
 Shot or Treated.
 Contractor. Burch Drlg.
 Issued. 11-7-59

County Graham
 KANSAS



Elevation. 2378' KB

Production. 57 BOPD

CASING:

8 5/8" 212' cem w/175 sx.
 5 1/2" 3939' cem w/125 sx.

Figures Indicate Bottom of Formations.

cement	210
shale & shells	1920
shale	1987
Anhydrite	2020
shale	2100
shale & lime strks	2505
lime & shale	3500
lime	3940 RTD
Total Depth	

TOPS:

Anhydrite (scout)	1987
Heebner	3663
Toronto	3687
Lansing	3699
Base Kansas City	3919

DST #1 3761-3790', op 1 hr., rec. 240'
 gas, 85' oil & gas cut mud, 120' heavily
 oil and gas cut mud. 120' very muddy
 oil. IBHP 1255#/30 mins., IFP 40#,
 FFP 107#, FBHP 1141#/30 mins.

DST #2 3845-3880', op 30 mins., rec. 10'
 mud. IBHP 65#/30 mins., IFP & FFP 0#,
 FBHP 0#.