

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-01551

Company- D. G. HANSEN  
Farm- Hill City High School No. 4

SEC. 26 T. 9 R. 23W  
SW SW SE

Total Depth. 3915'  
Comm. 2-20-63 Comp. 3-2-63  
Shot or Treated.  
Contractor. C-G Drlg.  
Issued. 7-27-63

County Graham  
KANSAS



CASING:  
8 5/8" 200'  
5 1/2" 3910'

Elevation. 2405' KB

Production. 80 BOPD & 18% WTR.

Figures Indicate Bottom of Formations.

(All meas. taken from top of RB)

shale	1095
shale	1505
sand	1730
red bed	1805
red bed & shale	1978
anhydrite	2018
shale	2050
shale & shells	2520
lime & shale	3470
lime	3915
Total Depth	

TOPS: SAMPLE

Topeka	3432
Heebner	3651
Toronto	3674
Lansing	3685
Base Kansas City	3907

DST #1	3710-3726'
DST #2	3726-3740'
DST #3	3761-3774'
DST #4	3835-3850'
DST #5	3848-3870'
DST #6	3867-3890'