

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-01557

Company- BURCH DRIG. CO., INC.
 Farm- Hildebrand No. 1

SEC. 28 T. 9 R. 23W
 NW NW NE

Total Depth. 3948'
 Comm. 12-11-57 Comp. 12-20-57
 Shot or Treated.
 Contractor.
 Issued. 3-8-58

County Graham
 KANSAS



CASING:

8 5/8" 210' w/160 sx cem.
 4 1/2" 3934' w/150 sx cem.

Elevation. 2422' KB

Production. 238 BOPD

Figures indicate Bottom of Formations

clay, shale	225
shale, shells	1455
shale, lime strks	1764
shale, shells	2005
shale, lime strks	2010
Anhydrite	2065
shale, lime strks	2255
lime, shale	3735
lime	3935 FTD
lime ??	3948 CTD
Total Depth	

TOPS:

Heebner	3699
Toronto	3726
Lansing	3738

DST #1 3761-83 Open 1 hr.
 Rec. 100' HOC salt wtr. plus
 800' slightly OC salt wtr. BHP
 700#.

DST #2 3800-114 Open 1 hr.
 Rec. 160' oil plus 180' very
 HOC. BHP 830#.