

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02659

Company- BURCH DRILLING CO.
Farm- Hildebrand "A" No. 2

SEC. 28 T. 9 R. 23W
SE NW NE

Total Depth. 4461'
Comm. 4-12-58 Comp. 4-28-58
Shot or Treated.
Contractor.
Issued. 6-14-58

County Graham
KANSAS



Elevation. 2421' KB

Production. S W D W

CASING:

8 5/8" 225' cem w/160 sx.
5" 4282'

Figures Indicate Bottom of Formations.

clay & sand	225
shale & shells	2013
Anhydrite	2065
shale	2265
lime & shale	3725
lime	3941
lime & shale	4080
lime	4150
cherty lime	4255
cherty lime & Dolomite	4310
lime	4385
dolomite & chert	4412
lime	4461
Total Depth	

TOPS:

Heebner	3704
Toronto	3730
Lansing	3740
Base Kansas City	3970
Marmaton Sand	4158
Marmaton Chert	4090
Conglomerate Chert	4189
Arbuckle	4232

DST #1 3765-3795', op 1 hr, rec. 50' muddy saltwater. FBHP 580#.

DST #2 3802-3820', open 1 hr, rec. 12' mud, All pressures 0#.

DST #3 3872-3898', op 30 mins, rec. 3' mud FBHP 160#.

DST #4 3895-3903', op 1 hr, rec 6' mud, All pressures 0#.

DST #5 3907-3934', op 30 mins, rec. 10' mud. All pressures 0#.