

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-005-03259

Company- MAGNOLIA PETROLEUM CO.
Farm- E. A. Hildebrand No. 1

SEC. 28 T. 9 R. 23W
CW/2 SW NE

Total Depth. 3995'
Comm. 8-14-57 Comp. 9-13-57
Shot or Treated.
Contractor. Barnett Drig.
Issued. 12-14-57

County Graham
KANSAS



Elevation. 2437' DF

Production. State Pot. P 180 BOPD

CASING:

8 5/8" 554' cem w/350 sx
5 1/2" 3994' cem w/150 sx.

Figures Indicate Bottom of Formations.

clay	20
sand & clay	100
shells	125
shale	1100
sand & shale	1375
shale & shells	1410
shale	1580
sand	1750
shale	1965
shale & shells	2035
Anhydrite	2070
shale	2540
lime & shale	2785
lime	3325
lime & shale	3535
lime	3695
lime & shale	3765
lime	3799
lime	3995 RTD
Total Depth	

TOPS:

Heebner	3720
Toronto	3741
Lansing-Kansas City	3756
Base Kansas City	3977

DST #1 3777-99, tool failed.

DST #2 3777-3808, op 1 hr. good blow
g/58", TSTM, rec. 847' oil (gr. 35°). 360'
gas & HOCM, FP 60 - 440#, IBHP 1100#/20"
FBHP 1040#/20".

DST #3 3937-54, op 1 hr. fair blow, rec.
338' MSW, FP 36-170#, IBHP 1280#/20".
FBHP 670#/20".