

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-90569

Company- IMPERIAL OIL CO.
Farm- Denio No. 10

SEC. 31 T. 9 R. 23W
NE NW SW

Total Depth. 4035'
Comm. 9-20-64 Comp. 9-28-64
Shot or Treated.
Contractor. Imperial Oil
Issued. 12-5-64

County Graham
KANSAS



Elevation. 2480' K.P.

Production. 162 BOPD - NW

CASING:

8 5/8" 210' surf. w/175 sx cem.
5 1/2" 4035' w/125 sx cem.

Figures Indicate Bottom of Formations.

sand, shale	1843
Dakota sand	1854
shale, red bed	2096
Anhydrite	2132
shale, red bed	2345
shale, lime	3600
lime	3718
shale, lime	3850
lime	4035
Total Depth	

TOPS:	SAMPLE	ELEC.
Anhydrite	2096	
Heebner	3772	3774
Toronto	3796	3798
Lansing	3810	3812
B/Kansas City	4030	

DST #1- 3824-50' Op. 1 hr. Rec. 560'
of gas, 120' of heavily oil &
GCM, & 120' of oil & GCM. ICIP
1547#/20 min., IF 52#, FF 96#,
FCIP 1120#/20 Min.

DST # 2 - 3850-58' Op. 1 hr. Rec. 120' of
gas, 30' of slightly oil & GCM &
510' of salt wtr. ICIP 1362#/20 min.,
IF 37#, FF 260#, FCIP 1286#/20 min.

DST #3 - 3870-86' Op. 1 hr. Rec. 1800' gas
& 360' of gassy muddy oil. ICIP
970#/20 min., IF 52#, FF 126#, FCIP
895#/20 min.

DST # 4 Op 1 hr. Rec. 3000' of gas, 90'
of slightly oil and gas cut mud, 60' of
heavily oil and gas cut mud and 120' of
gassy muddy oil. ICIP 245# 20 min., IF
74#, FF 119#, FCIP 230# 20 min.

DST # 5 Op 30 min. Rec. 10' of mud. ICIP
708# 20 min., IF 37#, FF 37#, FCIP 238# 20 min.