

GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

DREILING OIL, INC.
Victoria, Kansas 67671

32-9-23W
W/2 NE SE

MAR 27 1971

WELL LOG

Company **Dreiling Oil, Inc.**
Route #2
Victoria, Kansas 67671
Farm **Butcher B No. 2**
Total Depth **4035'**
Comm. **2-5-71** Comp. **2-12-71**
Contractor **Dreiling Oil, Inc.**
Victoria, Kansas 67671

15-005-20417
Sec. **32** Twp. **9** Rng. **23 W**
Location **W/2 NE SE**
County **Graham**
Elevation: **2466'** **K. B.**
2463' **D. F.**
2461' **G. R.**

Casing Record
191' - 8 5/8"
4029.55' - 4 1/2"

Cement Record
150 sacks cement
175 sacks salt saturated cement

Production:
P 1880 + 40% water
Lava
GR 39

Figures Indicate Bottom of Formations

0'	130'	Top Soil & Sand
130'	145'	Sand
145'	191'	Blue Shale
191'	1040'	Shale
1040'	1710'	Shale
1710'	2070'	Shale
2070'	2107'	Anhydrite
2107'	2332'	Shale & Lime Streaks
2332'	2490'	Shale
2490'	2720'	Shale
2720'	2835'	Shale & Lime
2835'	2970'	Shale & Lime
2970'	3225'	Shale & Lime
3225'	3324'	Shale & Lime
3324'	3610'	Lime & Shale
3610'	3697'	Lime & Shale
3697'	3805'	Shale & Lime
3805'	3875'	Lime & Shale
3875'	3940'	Lime
3940'	3945'	Lime
3945'	3980'	Lime
3980'	4025'	Lime
4025'	4035'	Lime
4035'	T.D.	

Sample Logs
Anhydrite 2070
Joplin 3537
Heebner 3752
Jarvis 3779
Jansing 3792
BKC J 4023

STATE OF KANSAS)
)ss
COUNTY OF ELLIS)

I, Leo F. Dreiling, of the Dreiling Oil, Inc., upon oath states