


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-065-01574

Company- SKELLY OIL CO.
Farm- Law No. 1SEC. 34 T. 9 R. 23W
SE SE NETotal Depth. 4254 P.B. 4165
Comm. 6-25-51 Comp. 7-11-51
Shot or Treated.
Contractor. Deel Brothers
Issued. 10-13-51330' f EL & 330 F SL NE/4
County Graham
KANSAS

246(m)

Elevation. 2460 D.F.
SGC

Production. Pot. 1384 bbls.

Figures Indicate Bottom of Formations.

surface soil, sand, shale		3879-3882 & 3844-3855 1500 gals. acid
& shells	180	15%.
shale & shells	204	
shale	385	
sand w/shale strks	1350	
sand & shale	1500	
red bed, shale & shells	1980	
lime & shells	2115	
lime brkn & shale	2235	
shale & lime shells	2480	
lime & shells	2600	
shale w/strks of lime	2705	
shale & lime brkn	2750	
lime & shale	2790	
lime	2925	
lime & shale	3070	
lime	3330	
lime brkn & shale	3400	
lime	3820	
lime lgt gry slightly oolitic	3838	
lime	3873	
lime lgt gry xylm	3877	
lime	3895	
lime wh finely xylm	3900	
lime	3904	
lime wh finely xylm	3907	
lime	3909	
lime finely xylm & oolitic	3912	
lime	3914	
lime finely xylm & granular	3925	
lime	3939	
lime wh finely xylm	3952	
lime & congl.	4137	
sand med. grained quartzitic	4141	
Congl.	4229	
dolo. lgt gry med. xylm	4254	
Total Depth P.B.	4165	

Tops:

Heebner shale	3708
Lansing lime	3741
Congl.	4070
Arb. lime	4229

Producing form. Lansing lime 3822-3939

Acid:

7-22-51 750 gals. 3879-3882
7-25-51 750 gals. 3844-3855
7-28-51 1000 gals. 3823-3829

3820-3838 spotted por. & stain w/live oil.

3909-3912 lgt stain. & por. show " "

3914-3925 " " " " "

& odor.

4137-4141 Heavy stain & sat., poor. por.

Az. 3822-3826 500 gals. 15% acid & 108
bbls. oil to fill hole & flush.