

WELL LOG BUREAU-- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-045-02661


Company - HARRY GORE
Farm - Law

No. 3

SEC. 34 T. 9 R. 23W
SW NE SE

Total Depth. 4235
Comm. 6-11-51 Comp. 6-24-51
Shot or Treated.
Contractor. Veeder Supply & Development Co.
Issued. 7-21-51

County. Graham
KANSAS



CASING:

8 5/8" 225' cem w/150 sxs.

Elevation. 2456 (2nd)
2357

2457 (m)
Production. dry

Figures Indicate Bottom of Formations.

surface soil	40
shale	60
sand	100
shale, sand	175
shale	220
shale, shells	1020
sand, shale	1140
shale, shells	1170
shale, shells, sand	1550
sand, shale	1780
shale, shells	2020
anhydrite	2068
shale, shells	2120
shale, shells, red rock	2450
shale, shells	2500
lime, shale, some salt	2585
lime, shale	2760
lime	2810
lime, shale	3745
lime	3980
lime, shale	4055
lime, shale, cherty	4095
conglomerate	4130
conglomerate cherty	4210
lime	4235
Total depth	

Tops:

Topeka	3491
Heebner shale	3708
Dodge Lime	3730
Lansing Kansas City	3741
Base Kansas City	3968
Marmaton Conglomerate	4065
Marmaton Sand	4140-46
Cherty Conglomerate	4159
Arbuckle	4210

Plugged at 200' w/15 sxs. cem.
Plugged at 40' w/10 sxs. cem.