

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-02137

Company- BURCH DRILLING COMPANY, INC.
Farm- Ella Law Estate No. 1

SEC. 34 T. 9 R. 23W
NW NW NW

Total Depth. 3975'
Comm. 1-24-58 Comp. 2-2-58
Shot or Treated.
Contractor. Burch Drilling Company, Inc.
Issued. 3-22-58

County Graham
KANSAS



CASING:
8 5/8" 220' cem w/170 sx

Elevation. 2432' KB

Production. Dry

Figures Indicate Bottom of Formations.

clay & soil	225
shale & shells	1375
shale & lime streaks	2010
shale	2011
Anhydrite	2048
shale & lime streaks	2568
shale & lime	3765
lime	3975-RTD
Total Depth	

TOPS:
Heebner 3711
Toronto 3734
Lansing 3749
Base Kansas City 3967

D.S.T. #1, 3769-85 1 hr. Rec. 7' mud. BHP 180#.
D.S.T. #2, 3814-26 Misrun.
D.S.T. #3, 3814-26 Misrun.
D.S.T. #4, 3814-26 1 hr. Rec. 21' mud. BHP 820#.
D.S.T. #5, 3810-26 1 hr. Rec. 13' mud. BHP 710#.
D.S.T. #6, 3870-95 1 hr. Rec. 14' mud. BHP 0#.
D.S.T. #7, 3894-3915. 1 hr. Rec. 12' mud. BHP 0#.
D.S.T. #8, 3919-34. 1 hr. Rec. 15' mud. BHP 0#.
D.S.T. #9, 3935-75. 1 hr. Rec. 5' mud. BHP 0#.