

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-005-01578

Company- AMERADA PETROLEUM CORP.
Farm- Margaret Diebolt **No.** 3

SEC. 35 **T.** 9 **R.** 23W
 NW SE SW

Total Depth. 3975
Comm. 7-31-51 **Comp.** 8-15-51
Shot or Treated. ✓
Contractor. Peel Brothers
Issued. 5-3-52

County Graham
KANSAS



CASING:

8 5/8" 214' cem.
 5 1/2" 3974' cem.

Elevation. 2444

Production. 1857 bbls. &
 12% wtr.

Figures indicate Bottom of Formations.

clay & shale	40
sand	65
sand & gravel	160
shale	340
shale & shells	838
sand, shale strks	1180
sand & shale	1400
red bed & shale	1998
anhyd.	2037
shale & shells	2135
lime brkn & shale	2375
lime & shale	2630
lime brkn & shale	2755
shale & lime	3066
lime sdy	3115
lime & shale	3424
sand & shale	3430
lime & shale	3470
lime	3510
lime & shale	3600
lime	3712
shale & lime	3725
lime	3975
Total Depth	

Geos: Sch.	
Topoka	3468
Heobner	3686
Mansing	3721
Brown lime	3988

D.S.T. 3730-65, open 2 hrs., Rec.
 Est. 25,000 cu ft. gas 2700' fluid, 213'
 oil cut mud; 2335' oil; 30' salt wtr, 1250#
 BHP.

D.S.T. 3770-3965, open 2 hrs., Rec. Est.
 15,000 cu. ft. gas, 75' oil cut mud;
 122' oil; 366' mud cut oil; 1057' mud
 cut oil, 30' oil & wtr, cut mud, 1270#
 BHP D.S.T. 3862-3950, open 2 hrs., Rec.
 208' sl. gas & oil cut mud; 0# BHP