

APR 19 1969

35-9-23W

WELL LOG

15-000-00202

OPERATOR: DANE G HANSEN TR

WELL NAME: #5 RICE EST. LOCATION: NE NE NW SEC 35-9S-23W

COUNTY: GRAHAM STATE: KANSAS

WELL COMMENCED: JAN 28, 1969 WELL COMPLETED: FEB 5, 1969

ELEVATION: 2416 KB TOTAL DEPTH: 3940'

PRODUCTION: OIL WELL RIG NO: 1

CASING - 8-5/8": 197.68' 10 JOINTS W/150 SACKS QUICKSET

~~XXXXXX~~ 4 1/2" 3948.04' 124 JTS. 9.5# NEW CASING W/150 SACKS
POZ SALT SAT. 60-40

ALL MEASUREMENTS TAKEN FROM THE TOP OF ROTARY BUSHING:

		DEVIATION		REMARKS:
FROM	TO	FORMATION	FROM VERTICAL	
197	1490	SHALE	1/2°	1000'
1490	1690	SAND	2-1/4°	1545' DST #1 3720-3745'
1690	1996	SHALE	2°	1800' DST #2 3775-3793'
1996	2031	ANHYDRITE	1-1/2°	2020' DST #3 3815-3847'
2031	2525	SHALE & SHELLS	1°	2220' DST #4 3878-3903'
2525	3735	LIME & SHALE	1°	2395'
3735	3940	LIME	1°	2580'
			3/4°	2790'
			1/4°	3325'