


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
503 East Murdock, Wichita, Kansas

Company- CHAMPLIN OIL & REFG. CO.
 Farm- Clara Rice "A" No. 1

SEC. 36 T. 9 R. 23W
 SE SE NW

Total Depth. 3964'
 Comm. 9-30-57 Comp. 10-14-57
 Shot or Treated.
 Contractor. Garvey Drlg. Co.
 Issued. 4-12-58

County Graham
 KANSAS



CASING:
 8 5/8" 254.47' w/200 sx cem.
 5 1/2" 3961' w/125 sx cem.

Elevation. 2402' DF

Production. 160 BOPD

Figures indicate Bottom of Formations.

sand, shale	257
shale, sand	1700
sand	1973
Anhydrite	2010
shale, shells	2530
shale, lime	2830
lime	3947
lime, shale	3964
Total Depth	

TOPS:	Elec.
Heebner	3638
Toronto	3660
Lansing	3674
Zone "G"	3756
Zone "H"	3810
Zone "I"	3832
Zone "J"	3848
Zone "K"	3868
Zone "L"	3890
Base Kansas City	3904

DST #1-3744-3785, open 2 hrs., good blow for 2 1/2 mins. and died. Rec. 20' watery mud. Tool plugged after the 2 1/2 mins.

DST #2-3744-85, ope 2 hrs., good blow thouout. Rec. 350' gas in drill pipe, 270' GCM with specks oil, 240' HO and GCM, 990' wtr and GCO. IFP-180#, FFP-740#, ISIP-1160#, FSIP-1060#.

DST #3-3814-45, open 2 hrs., gas to surface in 20 mins., too small to measure. Rec. 3185' free oil. no wtr. IFP 580#, FFP 1130#, ISIP 1390#, FSIP 1360#.

DST #4-3850-62, open 2 hrs., gas to surface in 40 mins., too small to measure. Pulled 12 stands, rec. oil, shut down. Rec. 3145' free oil, no wtr. IFP 280#, FFP 1000#, IBHP 1200#, 15 mins., FBHP 1110#, 60 mins.

DST #5-3871-87, open 2 hrs., weak blow for 5 mins., then intermittent weak blow for 35 mins., then steady weak blow for remaining 1 hr. and 20 mins. Rec. 45' slightly oil cut mud. IFP 0#, FFP 0#, ISIP 0# in 1t mins., FSIP 320# in 60 mins.

Perf; 3850-56 (Zone "J") Swabbed 167 Bbls. clean oil and light show of gas in 9 hrs.