

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-065-01593

Company- CHAMPLIN REFG. CO.
Farm- Keith No. 3

SEC. 4 T. 9 R. 24W
SE SW SE

Total Depth. 3998'

Comm. 1-16-55

Comp. 3-4-55


Shot or Treated.

Contractor. Armer Drlg. Co.

Issued. 3-26-55

County Graham

KANSAS



Elevation. 2414' DF

Production. 243 BO

CASING:

8 5/8" 215' w/150 sx cem.

5 1/2" 3996' w/150 sx cem.

Figures indicate Bottom of Formations.

surface clay-sand	216
shale-shells	2110
Anhydrite	2150
shale-red bed-shells	2295
shale-shells	2505
shale-lime	2650
shale-shells	2850
shale-lime	3735
lime	3985
shale	3998
Total Depth	

Schlumberger TOPS:

Heebner	3712
Lansing-Kansas City	3751
B/Kansas City	3977
Schlumberger T.D.	3998

D.S.T. - #1- 3773-94- Open
1 hr. Rec. 40' v. sl. o.
c. mud. BHP 1200#

D.S.T. - #2 - 3900-10- Open
1 hr. Rec. 1260' gas, 215'
free oil, 30' v.h.o.c. mud,
BHP not recorded.

D.S.T. - #3 - 3924-32- Open
1 hr. Rec. 4' mud. BHP 95#.

D.S.T. - #4 - 3966-85- Open
1 hr. Rec. 4' mud. BHP 195#.

Perf. 3906-10, Swb. 1 1/4 BOPH
for 18 hrs.
A/3000, Swb. 18 1/2 NOPH for 5
hrs.