

APR 4 1970

CONTRACTOR'S WELL LOG

15-005-20311

7-9-24W
S W S W S E

CONTRACTOR:
OPERATOR:
WELL NAME:
LOCATION:


Abercrombie Drilling, Inc.
Abercrombie Drilling, Inc.
MINIUM #1
440' N S/L & 440' E W/L
SE/4, Sec. 7-9S-24W
Graham County, Kansas
March 12, 1970
March 20, 1970
Jack K. Wharton

SPUD DATE:
COMPLETION DATE:
GEOLOGIST:

Dry/LK

0	40	Clay
40	75	Hard Sand and Gravel
75	140	Clay
140	318	Shale
318	1116	Shale and Shells
1116	1150	Shale
1150	1400	Dakota Sand
1400	1775	Shale
1775	1934	Sand
1934	2177	Shale (Red Bed)
2177	2211	Anhydrite
2211	2438	Shale and Shells
2438	2775	Shale
2775	3405	Shale and Lime
3405	3897	Lime and Shale
3897	4062	Lime
	4062	Rotary Total Depth

anhydrite 2177



Drilled 318' of 9" surface hole and set 7" csg. @310' w/100 sx. cement. Plug was down at 7:00 p.m., 3-12-70.
Dry & Abandoned.

FORMATION SAMPLE TOPS

ELEVATION

T/Anhydrite	2177	(+ 320)	2497 K.B.
Heebner	3800	(-1303)	2495 D.F.
Toronto	3825	(-1328)	2489 G.L.
Lansing	3840	(-1343)	
R. T. D.	4062	(-1565)	

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Jerry A. Langrehr, President of Abercrombie Drilling, Inc., does hereby state that the above and foregoing is a true and correct copy of the log of the Minium #1, located 440' North of the South Line and 440' East of the West Line of the Southeast Quarter, Sec. 7-9S-24W, Graham County, Kansas.