

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH


API No. 15 — 065 — 20,785
County Number

S. 11 T. 9 R. 24 ^K/_W

Loc. NW NE NW

County Graham

640 Acres
N



Locate well correctly

Elev.: Gr. 2414'

DF 2416' KB 2419'

Operator
Barnett Oil, Inc.

Address
1625 Vickers KSB&T Building Wichita, Kansas 67202

Well No. # 1 Lease Name Bell

Footage Location
feet from (N) (S) line _____ feet from (E) (W) line _____

Principal Contractor Dreiling Drilling Company Geologist R. B. Gebhart, Jr.

Spud Date 10/14/75 Total Depth 4020' P.B.T.D. _____

Date Completed 10/21/75 Oil Purchaser Clear Creek, Inc.

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		178'	common	150	quick set
Production	7 7/8"	4 1/2"	9 1/2#	4019'	common	125	2% gel, 10% salt

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			5	jets	3922-3925

Size	Setting depth	Packer set at
2 3/8"	3975'	_____

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
1,000 gal., 15% HCL	3922-3925

INITIAL PRODUCTION

Date of first production 1/3/76 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio
	<u>84</u> bbls.	---- MCF	---- bbls.	---- CFPB

Disposition of gas (vented, used on lease or sold) --- Producing interval(s) Lansas-Kansas City 3922'-3925'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Barnett Oil, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:
Oil

Well No.

1

Lease Name

Bell

S 11 T 9 S R 24 ^W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Top Soil	0	20	Anhydrite	2081 (+ 338)
Sand-Gravel	20	95	B/Anhydrite	2117 (- 302)
Shale	95	1615	Topeka	3501 (-1082)
Sand	1615	1825	Heebner	3717 (-1298)
Shale	1825	2081	Toronto	3742 (-1323)
Anhydrite	2081	2117	Lansing	3757 (-1338)
Shale	2117	3042	B/KansasCity	3971 (-1552)
Shale & Lime	3042	3510	RTD	4020 (-1601)
Lime	3510	4020		
T.D.	4020			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Dale P. Jewett
 Dale P. Jewett Signature
 Operations Manager

January 16, 1976 Title
 Date

L91L9

