

KANSAS DRILLERS LOG

WICHITA BRANCH

API No. 15 — 065 — 21,137
County Number

Operator

Donald C. Slawson

Address

200 Douglas Building Wichita, Kansas 67202

Well No.

1

Lease Name

Hildebrand 'A'

Footage Location

1140' feet from (N) (S) line 1650' feet from (E) (W) line

Principal Contractor

Slawson Drilling Co., Inc.

Geologist

Ralph Ruwwe

Spud Date

June 18, 1979

Total Depth

4035

P.B.T.D.

NA

Date Completed

June 26, 1979


Oil Purchaser

NA

S. 13 T. 9 R. 24W E W

Loc. SW NE NW

County Graham

640 Acres
N

Locate well correctly

Elev.: Gr. 2414

DF 2416 KB 2419

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	226'	60/40 poz	180 sx	2% gel; 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, gas lift, etc.)
RATE OF PRODUCTION PER 24 HOURS	Oil Gas Water Gas-oil ratio
	bbls. MCF bbls. CFPB
Disposition of gas (vented, used on lease or sold)	Producing interval (s)

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator DONALD C. SLAWSON		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Hildebrand 'A'	Dry Hole
S 13 T 9 R 24W E W		

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
0 - 231 Surface 231 - 2830 Shale 2830 - 3820 Shale and Lime 3820 - 4035 Lime 4035 RTD			<u>LOG TOPS</u> ANHY 2076 (+343) B/ANHY 2110 (+309) HEEB 3729 (-1310) TOR 3754 (-1335) LANS 3772 (-1353) MUN CRK 3887 (-1468) B/KC 3992 (-1571) LTD 4031 (-1612)	
DST #1 3834-3859 (90' Zn) 30-60-45-75, WB incr to SB, Rec. 190' CGO, 75' OCM (35% O) 50' MW. IFP 31-84#, ISIP 844#, FFP 94-146#, FSIP 813#, 106°.				
DST #2 3949-4002 (200-220' Zn) 30-60-30-45, V-WkB/30", Rec. 15' M, NS. IFP 31-42#, ISIP 1011#, FFP 42-42#, FSIP 668#.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 J.C. REMSBERG - Engineer August 30, 1979
	Signature Title Date

5976L9

WELL LOG

13-9-24W.

OPERATOR: Donald C. Slawson
200 Douglas Building
Wichita, Kansas 67202

LEASE: #1 Hildebrand 'A'
SW NE NW of Sec. 13-9-24W
Graham County, Kansas

CONTRACTOR: Slawson Drilling Co., Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: June 18, 1979

COMPLETED: June 26, 1979

CASING: Surface - 8 5/8" @ 226' w/180 sx 60/40 poz

0 -	231	Surface
231 -	2830	Shale
2830 -	3820	Shale and Lime
3820 -	4035	Lime
4035		RTD

STATE OF KANSAS)
)
COUNTY OF SEDGWICK) SS.

I, J.C.REMSBERG, of the Slawson Drilling Company, Inc. upon oath state that the above and foregoing is a true and correct copy of the log of the #1 Hildebrand 'A' test.


J.C. REMSBERG