


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company: IMPERIAL OIL OF KANSAS, INC.
Farm: Nickelson No. 1

SEC. 15 T. 9 R. 24W
C NE NE

Total Depth, 4058
Comm. 5-1-57 Comp. 5-13-57
Shot or Treated.
Contractor, Harms-Burt Drilling Co.
Issued. 7-20-57

County Graham
KANSAS



Elevation. 2497 RB

Production. 785 BOPD, NW

CASING:

8 5/8 @ 193' w/ 150 sx cmt.
5 1/2 @ 4058'

Figures indicate Bottom of Formations.

sand & gravel	160
shale	910
shale & sand	1480
shale	2149
anhydrite	2190
shale & shells	2540
shale & lime	3695
lime	4058
Total Depth	

TOPS:

Anhydrite	2149
Heebner	3796
Toronto	3821
Lansing	3836

DST #1: 3858-68, open 1 hr. rec. 135'
oil, 65' HOcm, BHP 1360#

DST #2: 3895-3908, open 2 hrs. rec.
1200' gas, 658 HOcm, 240' oil, BHP
1260#

DST #3: 3908-13, open 1 hr. rec. 1440'
SW w/ scum oil, BHP 1200#

DST #4: 3980-4000, open 1/2 hr. rec.
1600' gas, 120' HOcm, BHP 1000#

DST #5: 4006-24, open 40 min. gas to
surf. 40 min. rec. 1220' oil, BHP
1190#

DST #6: 4023-58, open 1 hr. rec. 12'
mud, BHP 30#