

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-00613

Company- BURCH DRILLING CO.
Farm- Mitchell No. 1

SEC. 20 T. 9 R. 24W
SE SE SW

Total Depth. 4115'
Comm. 2-3-58 Comp. 2-12-58
Shot or Treated.
Contractor.
Issued. 7-26-58

County Graham
KANSAS



CASING:
8 5/8" 220' cem w/170 sx.
4 1/2" 4114' cem w/150 sx.

Elevation. 2528' KB

Production. 31 BOPD

Figures indicate Bottom of Formations.

clay & sand	226
shale & shells	1900
shale, lime streaks	2177
anhydrite	2220
shale & lime	3870
lime	4115 RTD
Total Depth	

TOPS:
Heebner 3833
Toronto 3859
Lansing 3874
Base Kansas City 4104

DST #1 3868-90, 1 hr, rec. 1340' salt wtr.
BHP 1050#.

DST #2 3895-3922, 1 hr, rec. 395' salt wtr.
BHP 1220#.

DST #3 3937-60, 1 hr, rec. 220' salt wtr.
BHP 1320#.

DST #4 4002-45, 1 hr, rec. 60' watery mud.
BHP 1190#.

DST #5 4042-65, 1 hr, rec. 1' oil, 10'
heavy oil cut mud, 80' oil cut mud.
BHP 510#.

DST #6 4065-86, 1 hr, rec. 40' mud.
All pressures zero.