

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

15-0605-20057

COMPANY **LEBEN DRILLING**


SEC. 20 T. 9 R. 24W

FARM **Nickelson** NO. 1

LOC. SE SE SE

TOTAL DEPTH **4087'**
 COMM. **6-24-67** COMP. **7-2-67**
 SHOT OR TREATED
 CONTRACTOR **Leben Drilling**
 ISSUED **8-19-67**

COUNTY **Graham**



CASING

20	10	
15	8	5/8" 200' cem w/ 150 sx
12	6	
13	5	

ELEVATION **2513' KB**

PRODUCTION **Dry/ Lans**

0	180	Clay, Sand		
180	480	Shale	TOPS: SMP	
480	1720	Shale, Sand	Heebner	3820
1720	2180	Redbed	Toronto	3843
2180	2217	Anhydrite	Lansing	3857
2217	2400	Shale		
2400	3010	Shale, Lime		
3010	3565	Lime, Shale		
3565	4087	Lime		
	<u>4087</u>	<u>RTD - D. & A.</u>		

8 5/8" 8 rd. 20# new surface casing set @ 200' with 150 sacks of Common, 2% cc

I, Leslie Kite, do hereby certify that the above and foregoing is a true and correct copy of the log of the Nickelson #1 Well, located SE SE SE of Section 20, Township 9 South, Range 24 West, Graham County, Kansas, this 7th day of July, 1967, according to the records of Leben Drilling, Inc.

Leslie Kite
 Leslie Kite

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 7th day of July, 1967.

Ulanda Nichols
 Ulanda Nichols