

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-065-00561

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Wittman "A" No. 2

SEC. 20 T. 9 R. 24W
 C SE NW

Total Depth. 4092'

Comm. 9-8-58

Comp. 9-17-58


Shot or Treated.

Contractor. Imperial Oil of Kansas, Inc.

Issued. 11-15-58

County Graham

KANSAS



CASING:

8 5/8" 231' w/150 sx. cem.

Elevation. 2537 RB

Production. Dry

Figures Indicate Bottom of Formations.

sand and shale	231
shale, shells and sand	2140
anhydrite	2229
shale and shells	2655
shale and lime	3830
lime	4092 RTD
Total Depth	

TOPS:

Anhydrite	2190
Heebner	3831
Toronto	3856
Lansing	3869

DST #1 3892-3912 Open 1 hr. recovered
 5' mud, BHP 30#.

DST #2 3909-32 Open 1 hr. Recovered 5'
 mud, BHP 0#.

DST #3 3995-4025 Open 1 hr. Recovered
 10' mud, BHP 0#.

DST #4 4022-40 Open 1 hr.. Recovered
 12' mud, BHP 0#.

DST #5 4038-62 Open 1 hr. Recovered
 30' mud with specks oil, BHP 30#.

No Electric Log run