

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

15-065-00700

Company. HEATHMAN-SEELIGSON DRILLING CO.
 Farm- Keith No. 1

SEC. 21 T. 9 R. 24W
 SE SW SE

Total Depth. 4123

Comm. 10-9-55

Comp. 10-19-55

Shot or Treated.

Contractor. Heathman-Seeligson Drilling Co.

Issued. 11-26-55

County Graham
 KANSAS



8 5/8 @ CASING:
 172' w/ 125 sx cmt.

Elevation. 2505 DF

Production. Dry

Figures indicate Bottom of Formations.

clay & shale	40
sand & shale	172
shale & shells	314
shale & sand	1020
sand	1100
shale & sand	1240
shale & shells	1445
shale & red bed	1625
shale	1720
sand	1920
shale & red bed	2150
anhydrite	2191
shale	2215
shale & shells	2955
lime & shale	3695
lime	3810
lime & shale	3875
lime	4065
lime & shale	4123
Total Depth	

TOPS: (KB)

Anhydrite	2150
Heebner	3817
Toronto	3841
Lansing-KC	3856
Base K. C.	4075

DST #1: 3853-93, open 1½ hrs. rec.
 1560' wtr. IFP 200#, FFP 710#, BHP
 1220#

DST #2: 3893-3907, open 1½ hrs. rec.
 240' wtr. IFP 0#, FFP 140#, BHP 1390#

DST #3: 3980-4002, open 1½ hrs. rec.
 25' mud, IFP 15#, FFP 20#, BHP 1230#

DST #4: 4005-20, open 1 hr. rec. 5'
 mud, BHP 0#

DST #5: 4027-44, open 1 hr. rec. 10'
 mud, BHP 0#

DST #6: 4048-65, open 1 hr. rec. 5'
 mud, BHP 135#