

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


15-065-00544

Company- MURFIN, RAINS, & WILLIAMSON
Farm- Dreilling "C" No. 2

SEC. 28 T. 9 R. 24W
NE NE SW

Total Depth. 4140'
Comm. 12-3-58 Ccmp. 12-11-58
Shot or Treated.
Contractor. Murfin Drilling Co.
Issued. 1-24-59

County Graham
KANSAS



CASING:

3 5/8" @ 211' w/160 sx.

Elevation. 2543' KB

Production. Dry

Figures indicate Bottom of Formations.

surface hole	211
shale	625
shale & sand	900
shale - shells	1110
hard sand - shale	1300
shale - shells	1660
red bed	1900
sand - red bed	1995
anhydrite	2035
shale & shells	2200
shale & lime	3860
lime	4140
Total Depth	

TOPS:	
Anhydrite (Scout)	1995
Heebner	3654
Toronto	3878
Lansing	3890
Base/Kansas City	4120

DST #1 3887-97 Open 1 hr. Rec. 160'
muddy wtr. BHP 1235# in 20 min.

DST #2 4049-62 Open 1 hr. Rec. 90'
thin mud. IF 0#. FF 61#. BHP 1285#
in 20 min.