

L. J. DREILING AND SONS, INC.

Victoria, Kansas 67671

28-9-24W
SW SW NW

AUG 1 1970

WELL LOG

15-005-20334

Company Don E. Pratt Oil Operations
P. O. Drawer 370
Hays, Kansas 67601

Sec. 28 Twp. 9 Rng. 24 W

Farm Hoeting No. 1

Location SW SW NW

Total Depth 4155'

County Graham

Comm. 6-10-70 Comp. 6-17-70

Elevation: 2551' K. B.

Contractor L. J. Dreiling & Sons, Inc.
Victoria, Kansas 67671

2548' D. F.

2546' G. R.

Casing Record

230' - 8 5/8"
4147' - 4 1/2"

Cement Record

150 sac ks cement
200 sacks cement

Production:

P 135 BOPD + 25% with
LKC
GR 42.2

Figures Indicate Bottom of Formations

0'	135'	Top Soil & Sand
135'	160'	Sand
160'	165'	Iron ✓
165'	190'	Gravel
190'	238'	Blue Shale
238'	1150'	Shale & Sand
1150'	1765'	Shale & Sand
1765'	1975'	Sand
1975'	2015'	Redbed & Shale
2015'	2210'	Shale
2210'	2250'	Anhydrite
2250'	2505'	Shale
2505'	2880'	Shale with Lime Streaks
2880'	3124'	Lime & Shale
3124'	3403'	Shale
3403'	3590'	Lime & Shale
3590'	3728'	Lime
3728'	3862'	Lime
3862'	3922'	Lime
3922'	3940'	Lime
3940'	3990'	Lime
3990'	4000'	Lime
4000'	4056'	Lime
4056'	4078'	Lime
4078'	4096'	Lime
4096'	4155'	Lime
4155'	T.D.	



STATE OF KANSAS)

)ss

COUNTY OF ELLIS)

I, Leo F. Dreiling, of the L. J. Dreiling & Sons, Inc., upon oath states that the above and foregoing is a true and correct copy from the Daily Drilling Report from your Hoeting #1.