

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15-065-02157

Company- IMPERIAL OIL OF KANSAS, INC.
 Farm- Kohart "A" No. 2

SEC. 28 T. 9 R. 24W
 SW SW SE

otal Depth. 4110'
 omm. 7-13-57 Comp. 7-26-57
 hot or Treated.
 ontractor. Imperial Oil of Kansas, Inc.
 Issued. 9-14-57

County Graham
 KANSAS



CASING:
 8 5/8" 222' cem w/175 sx.

Elevation. 2535' RB

Production. Dry

Figures indicate Bottom of Formations.

sand & clay	170
shale & shells	970
shale & sand	1490
shale	1745
sand	1930
shale & red bed	2182
anhydrite	2220
shale & shells	2580
lime & shale	3865
lime	4110 RTD
Total Depth	

TOPS:

Anhydrite	2175
Hebbner	3836
Toronto	3858
Lansing	3871

DST #1 3867-74, open 1 hr., rec. 7' mud.
 BHP 180#.

DST #2 3866-79', open 2 hrs., recovered
 50' oil cut mud, 70' salt water.
 BHP 1160#. Zone judged no value.

DST #3 3991-4014', open 1 hr., recovered
 35' mud. BHP 1200#.

DST #4 4026-40', open 2 hrs., recovered
 12' mud with specks of oil. BHP 20#.

DST #5 4038-53', open 1 hr., recovered
 8' mud. BHP 20#.

DST #6 4038-67, open 2 hrs., recovered
 180' muddy salt water with specks
 of oil. BHP 825#.

DST #7 4062-84, open 1 hr., recovered
 50' mud. BHP 0#.