


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-005-02051

Company- TIME PET. ASSOCIATES & EMPIRE DRLG. CO. SEC. 33 T. 9 R. 24W
Farm- Chritchfield No. 1 C SE NW

Total Depth. 4100'
Comm. 7-16-63 Comp. 7-25-63
Shot or Treated.
Contractor. Empire Drilling Co.
Issued. 11-9-63

County Graham
KANSAS



Elevation. 2518' KB

CASING:

8 5/8" 158' cem w/85 sx.

Production. Dry

Figures Indicate Bottom of Formations.

surface-sand & shale	133
shale	665
shale & shells	1600
shale & sand	1910
shale-redbed	2161
Anhydrite	2199
shale	2330
shale & shells	2630
shale	2800
lime & shale	2865
lime	2990
lime & shale	3090
lime	3235
lime & shale	3825
lime & chert	3863
lime	3950
lime & shale	4000
lime	4027
lime & shale	4046
lime	4100 RTD
Total Depth	

TOPS: SCHLUMBERGER ELECTRIC LOG

Anhydrite (sample)	2161
Heebner	3823
Toronto	3845
Kansas City	3858
Base Kansas City	4087

DST #1 4004-27' Tool op 2 hrs. Weak blow for 20". Rec. 10' mud, no shows. IBHP 31#; FBHP 31#; IFP 28#, FFP 31#/30"

DST #2 Tool op 2 hrs. Weak Blow for 7" Rec. 15' mud, no oil. IBHP 78#, FBHP 39#; IFP 23#; FFP 39#/30"